

Goleta West Sanitary District
Hollister Avenue Interceptor



CLIENT CONTACT

Mark Nation
General Manager/Superintendent
Goleta West Sanitary District
Goleta, CA 93106
Phone 805.968.2617

PROJECT STATISTICS

Client Goleta West Sanitary District
Dates 2006–2010
Value of Services \$500K
Construction Costs \$3M

SERVICES PROVIDED

Civil Engineering

- Planning
- Final Design

PROJECT ELEMENTS

- permitting
- sewer
- traffic control
- utilities

PROJECT OVERVIEW

For this new 12-inch interceptor trunk sewer construction project, MNS provided engineering design for traffic control plans, project plans, specifications and estimates, surveying, construction management and inspection services. 7,000 ft of new trunk sewer line was installed along Hollister Avenue, including the construction of several manholes. Construction required extensive traffic control and shoring throughout the project. Coordination with permitting agencies such as the California Coastal Commission and City of Goleta was required. Reaching the sewer required trenching up to 20 feet in depth and

traversed numerous major utilities including high and low pressure gas lines, potable and reclaimed water lines, electrical transmission and distribution duct banks, and cable media fiber optic lines.

